

# NOvA technology

Jarek Nowak  
University of Minnesota





**NOVA: NuMI**

**Off-Axis**

**$\nu_e$**

**Appearance Experiment**

**180 Scientists and  
Engineers from 26  
Institutions**



**Near detector  
protoblock**

**Argonne National Laboratory - University of Athens - California Institute of Technology - University of California, Los Angeles - Fermi National Accelerator Laboratory - Harvard University - Indiana University - Lebedev Physical Institute - Michigan State University - University of Minnesota, Duluth - University of Minnesota, Minneapolis - The Institute for Nuclear Research, Moscow - Technische Universität München, Munich - State University of New York, Stony Brook - Northwestern University - University of South Carolina, Columbia - Southern Methodist University - Stanford University - University of Tennessee - Texas A&M University - University of Texas, Austin - University of Texas, Dallas - Tufts University - University of Virginia, Charlottesville - The College of William and Mary - Wichita State University**



# NOvA project

## NOvA – Totally Active Scintillator Detector

### Project elements

- **Fiber**
- **Scintillator**
- **PVC extrusions**
- **Detector modules**
- **Module assembly**
- **Photodetector**

### Other important

- **Buildings**
- **Software**
- **Beam**
- **Schedule to Data Taking**
- **Electronics**
- **Data Acquisition (DAQ)**



# NOvA experiment

- 2nd generation long baseline
- Use existing high intensity beam of muon neutrinos at Fermilab.
  - Construct two detectors off the main axis of the beam.
  - Location reduces background for the search.
- If neutrinos oscillate, electron neutrinos are observed at the Far Detector in Ash River, 810 km away.



## NOvA goals


The atmospheric mass scale:  $\Delta m^2_{32}$ .

Large mixing angle for atmospheric neutrino oscillations:  $\theta_{23}$ .

**The third mixing angle:  $\theta_{13}$ .**

**CP violation:  $\delta_{CP}$ .**

**Mass ordering for the atmospheric oscillations: the sign of  $\Delta m^2_{32}$ .**





# Near Detector

209 T

126 T totally active

23 T fiducial

1 blk - 78 modules


1 H plane = 3 modules

1V plane = 2 modules

Near Detector prototype built on the surface in NUMI off-axis beam.

Runs for ~1 yr

Near detector put in the NUMI beam tunnel off axis.




3 H modules

2 V modules



# Near Detector $\mu$ Catcher

- The Near Detector is backed up by 1 meter of steel, with standard modules interleaved.
- The  $\mu$  Catcher is now completely designed
  - Will be installed in the NDSB
  - Steel deliveries have delayed construction




- 10 layers steel, module
  - Last layer has 4 modules



# Far Detector

1000 planes , 380,000 channels  
15 kT mass (~85% fiducial)

- Cells are in 16-cell PVC extrusion.
- Glue 2 extrusions together to make a 32 cell module.
- 12 modules make up a plane.
- Planes alternate horizontal and vertical.



Simulated physicist




Extrusion cells in the near detector protoblock






# Detector Components


- Liquid scintillator (3 million gallons)
  - Contained in 3.9cm x 6.6 cm cells of length 15.6 meters
  - 3.9 cm as seen by the beam
- Cell walls are rigid PVC (5 kilotons)
  - Loaded with 15% anatase form of titanium dioxide
  - Diffuse reflection at walls keeps light near (within ~ 1 m) particle path
- Looped wavelength-shifting fiber collects light (11,160 km)
  - Fiber diameter 0.7 mm
  - Fiber shifts wavelength to ~ 520-550 nm along the fiber
- Avalanche photodiode (APD) converts light to electrical signal (11,160 devices, ea. 32 pixels)
  - 85% quantum efficiency



To 1 APD pixel



typical charged particle path





# Liquid Scintillator Composition

- Liquid scintillator for NOVA is composed of a primary scintillant (pseudocumene) that gives off light at 300 nm,
- waveshifters (PPO & bis-MSB) that downshift the UV photons to longer wavelength to facilitate absorption by the wavelength shifting (WLS) fibers (convert the photons to 420 nm),
- anti-static agent (Stadis) that prevents the build-up of static electricity.
- The “fluor mix” + anti-static are dissolved in a mineral oil solvent


	<b>component</b>		<b>mass fraction</b>
<b>solvent</b>	<i>mineral oil</i>	<b>liquid</b>	<b>94.90%</b>
	<i>pseudocumene</i>	<b>liquid</b>	<b>4.99%</b>
<b>fluor mix</b>	<i>PPO</i>	<b>powder</b>	<b>0.110%</b>
	<i>bis-MSB</i>	<b>powder</b>	<b>0.0015%</b>
<b>anti-static agent</b>	<i>Stadis-425</i>	<b>liquid</b>	<b>0.0010%</b>
	<b>Total</b>		<b>100.0%</b>




# WSL Fiber

**Need ~ 12,000 km of 0.7 mm diameter wavelength shifting fiber from Kuraray. So far ~10% received and tested**



- MSU Quality Assurance Scanner (duplicate at Kuraray factory)
  - Fiber wound on a drum in a 27 m long groove with holes on 1 m intervals
  - Fiber is NOT cut from the spool,
  - Light source illuminates fiber from within the drum
  - Total light output (photodiode) and spectrographic scans, each ~ 1 minute



**K27 dye @ 300 ppm, S-type**





Light Output at 15 m






# APD Description

- APD is a classic linear APD manufactured by Hamamatsu operated at a gain ( $M$ ) of 100
  - S11211(X) custom variant of commercial S8550 SiAPD
- Operating temperature is  $-15^{\circ}\text{C}$  to keep shot noise at the same level as the amplifier noise
- Signal-to-noise  $> 10$  for muon at far end of a 15m long cell
- Both ends of the fibers in each cell are read with a single APD
- 32 APDs in a single  $4 \times 8$  array to readout one module





Manufacturer	
Pixel Active Area	1.95 mm $\times$ 1.0 mm
Pixel Pitch	2.65 mm
Array Size	32 pixels
Die Size	15.34mm $\times$ 13.64mm
Quantum Efficiency ( $>525$ nm)	85%
Pixel Capacitance	10 pF
Bulk Dark Current ( $I_B$ ) at 25 C	12.5 pA
Bulk Dark Current ( $I_B$ ) at -15 C	0.25 pA
Peak Sensitivity	600 nm
Operating Voltage	$375 \pm 50$ volts
Gain at Operating Voltage	100
Operating Temperature (with Thermo-Electric Cooler)	$-15^{\circ}\text{C}$
Expected Signal-to-Noise Ratio (Muon at Far End of Cell)	10:1
APD channels per plane	384
APD arrays per plane	12
Total number of planes	930
Total Number of APD arrays	11,160
APD pixels total	357,120




Jar



# Tests of APDs



Gain=100 bias voltage *linear* vs. temperature




- Measured average QE with RMS spread across 32 channels
- Average across all channels  $(84.8 \pm 2.5)\%$  – expected 85%




# APD tests

## Bias V for Gain = 100



## Average Dark Current



- Bias voltage  $\sim 40$  V lower at  $-15^\circ\text{C}$  than  $+25^\circ\text{C}$
- Batch 1 APDs bias voltage lower than batch 2


- Average dark current  $\sim 20$ x lower at  $-15^\circ\text{C}$  than  $+25^\circ\text{C}$
- Batch 1 APDs average dark current  $\sim 10$ x lower than batch 2

Dark current at room temp about 0.2na (40x better than specification)



# PVC Extrusions

15% Anatase titanium dioxide





- All NDOS extrusions produced.
- Retooling for far detector extrusions (430 kg/hr)
- Production started in August 2010




# Technical details

- N-27 PVC Resin Compounder Contract in Place
  - PolyOne Corporation (Different than R&D Vendor Aurora Plastics)
  - Material has been tested and meets NOvA specification
- Extruding Vendor Contract in Place
  - Extrutech Plastics, Inc
  - Construction Dies and Tooling have been delivered
    - Tuning and testing since April
  - Expect die tuning to be completed in Sept. 2010
- Dimensions: Optical Metrology Machine
  - Flatness, Thickness and Shape
- Continuity of cell webs: Vacuum test
  - Alternate cells are placed under vacuum and others are at room pressure
- Structural and Material Strength
  - Test short (6") extruded samples
  - **Hydraulic pressure test** to failure ( ~150 psi )
    - Alternate cells pressurized
  - Drop-dart Impact test to measure of PVC ductility
- Reflectivity: Spectrophotometer
  - Measures reflectivity across scintillation spectrum
    - MC computes relative light output of module






# Module Architecture






# ND Manifold Architecture







# Raceway Functionality

Face of optical connector



- Registers fibers in optical connector
- Guarantees acceptable bend radius
- Shields fibers from events in manifold
- Facilitates assembly





Threading fibers  
into opt conn



# Production Factory

A Huge warehouse for module production and storage for both extrusions and modules.



Production is based on student labor.



Jarek Nowak, September 17, 2010



# Module Construction Process





# Module Construction Process



Inner glue



Inner seal



Leak testing inner seal



Outer seal



Leak testing outer seal



Painting





Stacking & packing

September 17, 2010





# Monitoring Fiber While Stringing

- Monitors fiber tension and light transmission as cells are strung
- Components
  - Light source
    - PVC tube with blue LEDs
    - Blinks at 10 Hz
  - Photodiode light sensor
  - Force meter



ANT2010, Santa Fe



John Kwong  
UMN






John Kwong, September 17, 2010



# End-Lit Fiber Tester


- Measures light transmission of threaded fibers
  - Bad fibers can be replaced (fibers not yet glued into optical connector)
  - Light is injected with blue laser and light is measured at the optical connector
  - Injection is highly localized and uniform across cells
  - Scan time = 40 seconds for 32 fibers
  - Fiber exposed to laser for ~0.5 seconds
    - Long exposure tests indicate no damage
- Components
  - 10 mW blue laser
  - Robot that moves the laser
  - Photodiode light sensor
  - Hot wire fiber cutter






# Types of Photos





1 - Top Lit



2 - Bottom Lit



3 - Center Lit (normal angle)




- Defects found by catching abnormal intensity of
  - Reflected light of angled light photos (1 & 2)
  - Transmitted light of angled light photos (1 & 2)
  - Light of normal angle light photo (3)



# Closed Module Tester


- To be used for final QA at factory and after arrival at far detector site
- Shine light on fiber ends and measure output intensity with a camera
- Components
  - Digital camera
  - Three LED lights
  - Shadow cap





# Near Detector Assembly

- Prototype Near Detector blocks have been assembled at ANL since April
- Five blocks are at FNAL, in position.
- Construction of the 6<sup>th</sup> will begin soon.




• Partially assembled block (4<sup>th</sup> of 6)

- Constructed at Argonne
- Raised in the MINOS service building
- The first mechanical prototype block (protoblock)

Lowering the protoblock into the MINOS shaft at FNAL



# Prototype Alignment



Scanner maps surface,  
multiple measurements

- One face of the protoblock, laser scanner test
  - This will be typical of the blocks -  $\sim 2.5$  mm range
  - The contour of both faces track each other.



# Summary

---

- 5 out of 6 blocks of the Near Detector are installed.
- The Integration Prototype Near Detector is extremely useful.
- Filling with liquid scintillator will start within a few weeks.
- The near detector will start taking data in November.
- The far detector production is on the schedule.